

TOTAL PAGU : Rp. 1.000.000.000,00 Referensi KBKI

	Jenis Barang/Jasa atau Keluaran	Satuan	Vol	Harga/Biaya	Pajak (%)	Total	Keterangan	Kunci Baris?	KBKI
1	U M U M		1	0	11	0			54 - 542
2	Mobilisasi	Ls	1	64.300.000,00	11	71.373.000,00			54 - 542
3	PEKERJAAN DRAINASE		1	0	11	0			54 - 542
4	Pemasangan Pipa 1 M PVC Class AW (Rucika Standard)	M	65	153.920,15	11	11.105.338,82			54 - 542
5	PEKERJAAN TANAH		1	0	11	0			54 - 542
6	Galian Biasa	M3	98,22	98.677,51	11	10.758.236,59			54 - 542
7	Galian perkerasan beraspal tanpa Cold Milling Machine	M3	49,7	747.171,18	11	41.219.192,49			54 - 542
8	Penyiapan Badan Jalan	M2	2.593,70	3.383,00	11	9.739.680,68			54 - 542
9	PEKERJAAN PERKERASAN BERBUTIR		1	0	11	0			54 - 542
10	Lapis Pondasi Agregat Kelas A	M3	172,01	990.588,28	11	189.134.109,95			54 - 542
11	PEKERJAAN PERKERASAN ASPAL		1	0	11	0			54 - 542
12	Lapis Resap Pengikat - Aspal Cair	Ltr	2.270,00	17.267,44	11	43.508.768,57			54 - 542
13	Lapis Perekat - Aspal Cair	Ltr	233,61	15.773,74	11	4.090.242,78			54 - 542
14	Lataston - Lapis Pondasi (HRS-Base) (gradasi senjang/semi senjang)	Ton	249,88	1.968.837,40	11	546.090.129,36			54 - 542
15	Bahan Anti Pengelupasan	Kg	49,98	63.091,88	11	3.500.198,70			54 - 542
16	PEKERJAAN STRUKTUR		1	0	11	0			54 - 542
17	Beton Mutu Sedang dengan fc = 20 MPa (K-250)	M3	35,32	1.773.187,45	11	69.518.168,61			
	Jenis Barang/Jasa atau Keluaran	Satuan	Vol	Harga/Biaya	Pajak (%)	Total	Keterangan	Kunci Baris?	KBKI

TOTAL NILAI (setelah pembulatan)

Rp. 1.000.000.000,00